



Ph.: 0361-2970214 (O)

**OFFICE OF THE PRINCIPAL**  
**HANDIQUE GIRLS' COLLEGE**  
**GUWAHATI - 781001, ASSAM**

**Dr. Ranjit Sarma, M.Sc., M. Phil, Ph.D.**  
**Principal-cum-Secretary**

e-mail : hgcollege75@gmail.com  
Website: www.hgcollege.edu.in

Ref. No. : HGC/ESTT/NIQ/2024/01/002

Date : 08.07.2024

### NOTICE INVITING QUOTATION

Sealed quotation on firm letterhead affixing a non refundable court fee stamp of Rs. 8.25 are hereby invited from the reputed registered firms/contractors of relevant categories having experience of execution of similar nature of constriction/renovation works as mentioned below at Handique Girls' College, Guwahati-01, Assam. The quotations along with GST Registration certificate, PAN Card, Trade License and Experience Certificate of execution of works of similar nature have to be submitted at the designated place at the Office of the undersigned. The sealed envelope must be superscribed with the Quotation Number and addressed to the undersigned. The quotation will be received by the Office of the Principal, Handique Girls' College up to **15<sup>th</sup> July, 2024, 2.00 pm** and will be opened on the same day at 3.00 pm. Contractor or one authorized person may be present at the time of opening.

1.	Name of Work	<b>Raise of the floor height (250 mm) of Chemistry Department, Handique Girls' College, Guwahati-01, Assam as per CPWD DSR 2021</b>
2.	Estimated amount	Rs.4,26,500.00
3.	Time of completion	30 days
4.	Earnest Money to be deposited with the quotation Paper	2 % of Estimated value for General Category and 1% of estimated value for SC/ST/OBC/MOBC Category.
5.	Security Deposit	Addition 3% of Estimated value (only by Successful bidder)


The Earnest and Security amount will have to be deposited by Demand Draft in the favour of Principal-Cum Secretary, Handique Girls' College, Guwahati, Payable at Guwahati. Quotations submitted by the bidders shall remain valid for acceptance for a period of 180 (one hundred eighty) days from the date of opening of such quotations. The bidder/s shall not be entitled to revoke or cancel his/their quotation/s or to vary any of the terms thereof during the said period of validity. The period of liability shall be 12 (Twelve) months reckoned from the date of issue of completion certificate on actual completion of the work. The taxes as per rule will be deducted at source from the total bill value. Quotation not properly sealed will be liable for cancellation.

Principal  
Handique Girls' College  
Guwahati-01, Assam

Memo No.: HGC/ESTT/NIQ/2024/01/002-A, Dated: 08.07.2024

Copy to:

1. Notice board/Website for display.
2. Convenor, Construction Committee for kind information.
3. Office file for record.

  
Principal  
Handique Girls' College  
Guwahati-01, Assam

**MEASUREMENT SHEET FOR RAISE THE FLOOR HEIGHT ( 250 MM) OF CHEMISTRY DEPARTMENT AT HANDIQUE GIRL'S COLLEGE, DIGHALIPUKHURIPAR, PANBAZAR, GUWAHATI AS PER CPWD DSR 2021**

SL. NO.	SOR I/No.	Description of Items	NO.	L	B	H	QTY	Unit	Rate	Amount
1	15.3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge								
		Floor	1	15	14.5	0.025	5.44	CUM		
						Total	5.44	CUM		
2	15.7	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.								
	15.7.4	In cement mortar cum								
		Wall Dismatle	1	14.5	0.15	0.8	1.74	CUM		
3	15.12	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :								
	15.12.1	Of area 3 sq. metres and below								
		Door	4	1.2	2.1		4.00	Each		
4	15.14.1	Dismantling wood work in frames, trusses, purlins and rafters up to 10 metres span and 5 metres height including stacking the material within 50 metres lead :								
		Of sectional area 40 square centimetres and above								
		Wood Frame	4	2.1	0.1	0.075	0.06	CUM		
5	2.27	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.								
		Sand Filling	1	14.5	15	0.14	30.45	CUM		
6	11.1	Brick on edge flooring with bricks of class designation 7.5 on a bed of 12 mm cement mortar, including filling the joints with same mortar, with common burnt clay non modular bricks:								
	11.1.2	1:4 (1 cement : 4 coarse sand)								
		Floor	1	14.5	15		217.50	SQM		
					Total	217.50	SQM			
7	11.3	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete								
		40 mm thick with 20 mm nominal size stone aggregate								
		Floor	1	14.5	15		217.50	SQM		

SL. NO.	SOR I/No.	Description of Items	NO.	L	B	H	QTY	Unit	Rate	Amount
8	5.2	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :								
	5.2.2	1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)								
		Lintel	1	14.5	0.15	0.125	0.27	CUM		
					Total	0.27	CUM			
9	5.9	FORM WORK Centering and shuttering including strutting, propping etc. and removal of form for								
	5.9.5	Lintels, beams, plinth beams, girders, bressumers and cantilevers								
		Lintel	1	14.5	0.15	2	4.35	SQM		
					Total	4.35	SQM			
10	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level								
		Thermo-Mechanically Treated bars of grade Fe-500D or more.								
		Lintel 10 MM	1	14.5	4	0.62	35.96	KG		
		Stirrup	2	0.5	115	0.39	44.85	KG		
					Total	80.81	KG			
11	13.4	12 mm cement plaster of mix :								
	13.4.1	1:4 (1 cement: 4 coarse sand)								
		Wall	1	14.5		1.2	17.40	SQM		
					Total	17.40	SQM			

Grand Total: